KADUR DIVISION.

Dated 3rd July 1908.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur Division, up to 15th August 1908, for improving the Ramanahalli channel in Chikmagalur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1910.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chikmagalur, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for improving the Ramanahalli channel in Chikmagalur Taluk", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of improving the Ramanahalli anicut, upper channel, from lower channel of Chikmagalur Taluk, Kadur District.

No.	*Items of work.*	*Per.*	*Quantity.*
	Improving the Head works.		
1.	Earthwork excavation	C yd.	7
2.	Burnt brick in surki	C. ft.	207
3.	Burnt stone slabs well dressed	S. ft.	370
4.	Plastering with surki	„	4·45
5.	Pointing with lime mortar	Sqr.	5·94
6.	Removing and refixing the available slabs	S. ft.	113
7.	Teakwood work, wrought and put up	C. ft.	11
8.	Providing new shutter including iron works and handles, etc., complete.	Each.	2
9.	Providing new shutter including iron works and handles, etc., gearing rods and spanners, etc., complete.	„	3
	Improving the upper channel with lower channel from junction to end.		
10.	Earthwork excavation and forming the same earth as bank and watering and tamping, etc., complete.	C. yd.	16,538
11.	Earthwork for embankment with a bed of two furlongs average including watering and tamping, etc., complete.	„	12,619
12.	Rough stone work, new	„	1,535
13.	Turfing	S yd.	7,532
	Upper channel (sundry items.)		
14.	Stopping the leaks in bank	L. S.	Rs.
15.	Removing jungle and trees	Each Fig.	20½
16.	Repairing breach in ⅔	L. S.	Rs.
17.	Repairs to madaboys 1	Each.	6
18.	Petty repairs to relieving weirs	No.	2
19.	Removing boulders in the channel	L. S.	Rs.
20.	Repairs to cattle bridge	No.	3
21.	Constructing a new cattle bridge as per enclosed estimate ..	L. S.	Rs.
	Lower channel (sundry items).		
22.	Removing boulders in the channel	„	„
23.	Re-constructing new madaboys as per enclosed estimate ...	No.	7
24.	Constructing a new cattle bridge as per enclosed estimate...	„	1
	Mile stone.		
25.	Providing new zero and mile stone including base slab cutting figures, and painting.	Each.	2
26.	Cutting check drain in ridge parallel to alignment of channel.	L. S.	Rs.

R. S. NAVARATHNA,
Exec. Engineer.